


Warsaw, Melcer Chamber Music Hall of the Uniwersytet Muzyczny Fryderyka Chopina

Okólnik 2, 00-368 Warsaw, Poland



Builder	Walcker
Year	ca. 1993
Period/Style	Neo-Baroque
Stops	18
Keyboards	2+P
Keyaction	tracker/mechanical
Sampleset	<u>Piotr Grabowski</u>

Description

The organ is located at The Fryderyk Chopin University of Music in Melcer Chamber Music Hall. It was built by Walcker company in 1993 together with other two instruments - big 55 stop organ in the concert hall and small 4 stop positiv. It got 15 stops (3 stops are borrowed) divided into 2 manuals and pedal. Manual compass is from C to g3, pedal from C to f. It got fully mechanical tracker action. Brustwerk division is enclosed.

Stoplist/Disposition

Hauptwerk	Brustwerk	Pedal
Nachthorn 8'	Gedackt 8'	Subbass 16'
Prinzipal 4'	Quintatön 8'	Gedacktbass 8'
Nasard 2 2/3'	Röhrflöte 4'	Choralbass 4' *
Oktave 2'	Prinzipal 2'	Oktave 2' *
Mixtur 1 1/3' 4f.	Quinte 1 1/3'	Trompete 8' *
Trompete 8'	Sifflöte 1'	
	Krumhorn 8'	

Additional: HW/BW, HW/Ped, BW/Ped, Tremulant BW, Schweller BW, * borrowed from Hauptwerk

Sources

<https://piotrgrabowski.pl/melcer-chamber-music-hall/>